

Prestressed Concrete Design (SAB 4323)

Composite Beams

Dr. Roslli Noor Mohamed



Innovative.Entrepreneurial.Global

ocw.utm.my





<u>Introduction</u>

- Composite construction implies the use, in a single structure acting as a unit, of different structural element made with similar or different structural materials.
- In a composite member where only concrete is used as a material, the concrete is placed in at least two separate stages generally leading to two different unit weights and/or properties.
- This is the case of composites made with precast reinforced or prestressed concrete element combined with a concrete element cast in situ at a different time.
- Typical composite cross-sections are as shown in the next slide





Typical Composite Cross-Sections





- Total construction time is substantially reduced when precast concrete elements are used.
- Pre-tensioning in plant is more cost-effective than post-tensioning on site. Because the precast prestressed concrete element is factory-produced and contains the bulk of reinforcement, rigorous quality control and higher mechanical properties can be achieved at relatively low cost. The cast in situ concrete slab does not need to have high mechanical properties and thus is suitable to field conditions.



- The precast prestressed concrete units are erected first and can be used to support the formwork needed for the cast in situ slab without additional scaffolding (or shoring)
- In addition to its contribution to the strength and stiffness of the composite member, the cast in situ slab provides an effective means to distribute loads in the lateral direction.
- The cast in situ slab can be poured continuously over the supports of precast units placed in series, thus providing continuity to a simple span system.





Temporary Slab Formwork







Permanent Slab Formwork







Shored Construction







Unshored Construction







Continuous Construction







Continuous Construction







<u>Construction Sequence And</u> <u>Loading Stages</u>

Loading Stage	Loads Considered in Shored Construction	Loads Considered in Unshored Construction	Section
1	αPi & Wsw	αPi & Wsw	Precast
2	βPi & Wsw	βPi, Wsw & Wslab	Precast
3	βPi,Wsw,Wslab, W _{DL} & W _{LL}	βPi,Wsw,Wslab, W _{DL} & W _{LL}	Composite





Transformed Section Properties

Need to consider

- Effective Flange Width
- Transformed Section





Effective Flange Width

 Only part of the slab participates in enhancing the strength and stiffness in the monolithic or composite beam-slab construction.





Effective Flange Width







<u>Transformed Vs Effective</u> <u>Flange Width</u>







Working Stresses







Working Stresses







Example 6-1

Determine the stress distributions at the various load stages of the floor slab shown below. Given the followings:

Span = 5m, Superimposed loads = 5 kN/m^2 , Unshored Construction

Prestress Force at Transfer = 24.3 kN/wire

Effective Prestress Force = 19.4 kN/wire

Section Properties:

A = $1.13 \times 10^5 \text{ mm}^2$, I = $7.5 \times 108 \text{ mm}^4$, $z_1 = z_2 = 6.0 \times 10^6 \text{ mm}^3$

fcu,precast = 40 N/mm², fcu,slab = 30 N/mm²







Solution

Load Stage 1 – Precast Section $e = 125 - 40 = 85 \text{ mm}, \alpha \text{Pi} = 6 \times 24.3 = 145.8 \text{ kN}$ 0.62 Beam self weight = $0.113 \times 24 = 2.7 \text{ kN/m}$ Mi = $2.7 \times 2.7^2/8 = 8.4 \text{ kNm}$ $f_1 = \frac{145.8 \times 10^3}{1.13 \times 10^5} - \frac{145.8 \times 85 \times 10^3}{6.0 \times 10^6} + \frac{8.4 \times 10^6}{6.0 \times 10^6}$ $f_1 = 1.29 - 2.07 + 1.40$ $f_1 = 0.62 \text{ N/mm}^2$ $f_2 = \frac{145.8 \times 10^3}{1.13 \times 10^5} + \frac{145.8 \times 85 \times 10^3}{6.0 \times 10^6} - \frac{8.4 \times 10^6}{6.0 \times 10^6}$ 1.96 $f_2 = 1.29 + 2.07 - 1.40$ $f_2 = 1.96 \text{ N/mm}^2$





Solution

Load Stage 2 – Precast Section β Pi = 6 x 19.4 = 116.4 kN Md = $8.4 + 0.075 \times 0.6 \times 24 \times 5^2/8 = 11.8 \text{ kNm}$ $f_1 = \frac{116.4 \times 10^3}{1.13 \times 10^5} - \frac{116.4 \times 85 \times 10^3}{6.0 \times 10^6} + \frac{11.8 \times 10^6}{6.0 \times 10^6}$ $f_1 = 1.03 - 1.65 + 1.97$ $f_1 = 1.35 \text{ N/mm}^2$ $f_2 = \frac{145.8 \times 10^3}{1.13 \times 10^5} + \frac{145.8 \times 85 \times 10^3}{6.0 \times 10^6} - \frac{11.8 \times 10^6}{6.0 \times 10^6}$ $f_2 = 1.03 + 1.65 - 1.97$

0.71

 $f_2 = 0.71 \text{ N/mm}^2$





<u>Solution</u>

Load Stage 3 – Composite Section

Difference of fcu between precast and composite = 10N/mm²

→Assume a modular ratio of 1 (non-transformed section)

- $y_2 = 1.13 \times 10^5 + (600 \times 75) / (1.13 \times 10^5 \times 125 + 600 \times 75 \times 288)$
 - = 171 mm

 $I \text{ comp} = 1.63 \text{ x} 10^9 \text{ mm}^4$

Bending Moment for imposed load,

 $M_{IL} = 0.6 * 5 * 5^2/8 = 9.4 \text{ kNm}$







Load Stage 3 – Composite Section







<u>Allowable Stresses in</u> Precast Section

Stage 1

• Flexural tensile stresses

 $f_{tt} = 1.0 \text{ N/mm}^2$ (Class 1 members)

 $f_{tt} = 0.45(f_{ci})^{1/2} \text{ N/mm}^2$ (Class 2, pre-tensioned)

 $f_{tt} = 0.36(f_{ci})^{1/2} \text{ N/mm}^2$ (Class 2, post-tensioned)

• Flexural compressive stresses

 $f_{ct} = 0.5 f_{ci} \text{ N/mm}^2$ (flexural members)

 $f_{ct} = 0.4 f_{ci} \text{ N/mm}^2$ (near uniform distribution of prestress)

Where f_{ci} is the concrete strength at transfer of prestress

(>= 25 N/mm² - Cl 4.1.8.1)





<u>Allowable Stresses in</u> <u>Composite Section</u>

Stage 2 & Stage 3

- Flexural tensile stresses (Only for precast member) $f_{ts} = 0 \text{ N/mm}^2$ (Class 1 members) $f_{ts} = 0.45(f_{cu})^{1/2} \text{ N/mm}^2$ (Class 2, pre-tensioned) $f_{ts} = 0.36(f_{cu})^{1/2} \text{ N/mm}^2$ (Class 2, post-tensioned)
- Flexural compressive stresses (Precast/Cast in situ member) f_{cs} = 0.33f_{cu} N/mm² (flexural members) f_{cs} = 0.4f_{cu} N/mm² (in statistically indeterminate structure) Where f_{cu} is the design compressive strength of concrete





Inequalities for the 3 Load Stages

Combining the stresses at the 3 load stages and their stress limits, the following 7 inequalities were obtained:



Adequacy of a Composite Section

Combining (31) and (35),

$$z_{1,beam} \geq \frac{\alpha(M_s - M_d)}{(\alpha f_{cs} - \beta f_{tt}) + \frac{1}{Z_1}(\beta M_i - \alpha M_d)} \dots \dots \dots (38)$$

Combining (32) and (36),

$$z_{2,comp} \geq \frac{\alpha(M_s - M_d)}{(\beta f_{ct} - \alpha f_{ts}) + \frac{1}{Z_2}(\beta M_i - \alpha M_d)} \dots \dots \dots (39)$$

Also from (37),



The range of prestressing force for a given e can be found from the following inequalities:

The inequalities sign in (41) & (43) will be reversed if the denominator becomes -ve





Magnel diagram can be plotted from the followings:

$$e \geq \frac{1}{\beta P_i} \left(M_d + \frac{Z_1}{Z_{1,beam}} (M_s - M_d) - Z_1 f_{cs} \right) + \frac{Z_1}{A} \dots (47)$$

$$e \geq \frac{1}{\beta P_i} \left(M_d + \frac{Z_2}{Z_{2,comp}} (M_s - M_d) + Z_2 f_{ts} \right) - \frac{Z_2}{A} \dots (48)$$





The following figure shows a cross section of a simply supported bridge made up of 6 nos JKR PRT2 class 1 precast post-tensioned prestressed beam and a 200mm cast in situ slab. Design the precast prestressed beam using the following information:

Span = 20.6m; Unshored Construction

Loading/beam: Wslab=8.11kN/m; SDL=3.73kN/m; LL=14.56kN/m

Beam: fci = 45N/mm²; fcu = 50N/mm²; E = 36 kN/mm²; A = 488350 mm²

y1 = 575.80 mm; y2 = 774.20 mm; I = 8.506 x 10¹⁰ mm⁴

Slab : fcu = 40N/mm²; E = 34 kN/mm²; h = 200 mm

Prestress Steel (12.9mm dia 7-wire super strand):

Fpu = 186 kN Aps = 100 mm² fpu = 1860 N/mm² %UTS = 70%





Solution



Modular ratio = 34/36 = 0.94 be the lesser of 20.6/5 = 4.12m and 1.104m Take be = 1104 mm btr = 0.94 * 1104 = 1042.7mm

Composite S	ection	btr =	1042.7 mm
m =	0.94	h _{comp} =	1550 mm
A _{comp} =	696883.3 mm²	I _{comp} =	1.52E+11 mm ⁴
y _{1,comp} =	573.6 mm	z _{1,comp} =	2.66E+08 mm ³
y _{2,comp} =	976.4 mm	z _{2,comp} =	1.56E+08 mm ³
y _{1,beam} =	373.6 mm	z _{1,beam} =	4.08E+08 mm ³







Solution





<u>Solution</u>

Moments

Check Section Adequacy







Solution

Minimum Prestressing Force

(z ₁ ftt - Mi)=	-795338048.2		z ₁ /A - e =	-230.5
(z ₂ fct + Mi)=	3119648793		z ₂ /A + e =	758.0
(z ₁ fcs - Md)=	1359652830		Num43 =	1.01E+09
(z _z fts+Md)=	1077808094		Num44 =	1.76E+09
P ₄₁ =	<=	3833.8	kN	
P ₄₂ =	<=	4573.1	kN	
P ₄₃ =	>=	-6077.0	kΝ	
P ₄₄ =	>=	3225.6	kΝ	
Pmin	=	3225.6	kN	

The range of prestressing force for a given e can be found from the following inequalities:







Magnel Diagram

e = m/Pi + c					
m	Nmm	kNmm	С	mm	
m ₄₅ =	883708942.5	883.709	C ₄₅ =	302.50	
m ₄₆ =	3466276437	3466.276	c ₄₆ =	-224.98	
m ₄₇ =	-1400762182	-1400.762	c ₄₇ =	302.50	
m ₄₈ =	2444898192	2444.898	c ₄₈ =	-224.98	
1/Pi (kN ⁻¹)	0.31002459	0.284463	0.256016		
Pi (kN)	3225.6	3515.4	3906		
No of Strand	24.8	27	30		
Fpu=	186	kN			
%UTS =	70	%			







Solution



ybar= 774.2 mm

row	Bil	Dist	Ay	
1	1	105	105	
2	1	240	240	
3	1	375	375	
4	0	0	0	
5	0	0	0	
6	0	0	0	
7	0	0	0	
8			0	
9			0	
10			0	
	3		720	
	yms =	240		

^{534.2} mm e =

<u>Arran</u>	gemen	t of	Tend	ons

No of stra	nds =	27	
No of strand / ca	9		
No of ca	ble =	3	
No of strand/r	row =	3	
Diameter of stra	and =	12.9	mm
	Aps =	100	mm²
Dia of duct: The large	er of		
(4*1	2.9 + 6) =	57.6	mm
and (4*1.5*1	$00/\pi)^{1/2} =$	13.8	
	==>	57.6	mm
	Use	60	mm
Duct Spacing:	Sy =	60	mm
	Sx =	60	mm
Use Sx =	Sy =	75	mm

The arrangement of cables produced a new value of e = 534.2mm (old e = 533mm). From Magnel Diagram, this value is still within the safe zone.









Ultimate Strength

Remember to consider the followings:

- Ultimate Flexural Strength
- Ultimate Shear Strength
 - Horizontal Shear
 - Vertical Shear